



வ.உ.சி.துறைமுக ஆணையர்  
वी.ओ.सी.पत्तन प्राधिकरण  
V.O.C Port Authority

Global Connect

MINISTRY OF PORTS, SHIPPING AND WATERWAYS GOVERNMENT OF INDIA  
CIVIL ENGINEERING DEPARTMENT  
ADMINISTRATIVE OFFICE, HARBOUR ESTATE,  
TUTICORIN – 628 004, TAMIL NADU

Telephone : 0461-2352252  
Email : [ce@vocport.gov.in](mailto:ce@vocport.gov.in)  
Website : [www.vocport.gov.in](http://www.vocport.gov.in)

### **NIT (LIMITED TENDER)**

(Ref:Lr.No.CIV-MTCB2-MNT-REPLA-V1-25/D.1666 Dated:30.05.2025)

Sub: Replacing the Welcome Board of Check Post No.1 at VOC Port –  
Limited tender invited – (Put to tender value -Rs.4,70,925/-)

VOC Port Authority, Tuticorin desires to invite Limited tender from the following five  
Port Civil Engineering Contractors / firms.

1. Shri.R.T.Vairamuthu, Tuticorin-2
2. M/s. Shri Balaji Construction, Tuticorin-2
3. M/s.KSR Construction, Tuticorin-2
4. M/s.Maharaja Engineering Contractor, Tuticorin-2
5. M/s.Shri.Venkateswara Constructions, Tuticorin-8

The above firms shall submit their duly filled-in Price Quote Schedule in a sealed cover on or before 05.06.2025 up to 15.00 hrs to the office of the undersigned in person. The Price Quote received will be opened on 06.06.2025 @15.30hrs.

As it is a Limited Tender Enquiry from the above five firms only, the bids from any other firms will not be considered.

This issues with the approval of Competent Authority.

Encl: Price Quote Schedule.

  
30/05/2025  
**EXECUTIVE ENGINEER  
(RCM & BMR DIVISION)**

**Name of Work: Replacing the Welcome Board of Check Post No.1 at VOC Port**

(Ref:Lr.No.CIV-MTCB2-MNT-REPLA-V1-25/D.1666 Dated:30.05.2025)

**PRICE SCHEDULE**

Name of Bidder					
Sl. No	Qty	Unit	Description of work	Rate/unit in figure & words	Amount
1	395	Sqm	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineerin- charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.		
2	104	Sqm	Dismantling the old Aluminium Composite Panel (ACP) & Providing and fixing of new Aluminium Composite Panel (ACP) on the existing frame work designed extruded sections and fabricated fixed at all level elevation and heights. Rate shall included 3mm thick ACP sheet (0.20 + 2.60 + 0.20) alstrong or equivalent fixing with spacer tape and the ACP sheet bounded with special type structural sealant of dow corning 789 or equivalent in dust free conditions the gaps between ACP sheet to be filed with whether sealant and backer rod or 12mm foam sheet to ensure water and air tightness, necessary clamps,fasteners, bolt nuts etc. in all complete complying with standard specification as directed by the departmental officers.		

3	35	Sqm	Supplying & fixing Retro-reflective sticker for letters on Aluminium Composite Panel (ACP) board at all level elevation and heights. The cost exclusive of scaffolding charges & Inclusive of materials, labour charges & conveyance etc., Complete and as directed by the Engineer in-Charge.		
				<b>Total Rs.</b>	

Contractor's Signature with Seal