



வ.ஓ.சி. துறைமுக அதிகாரம்
वी.ओ.सी. पत्तन प्राधिकरण
V.O.C Port Authority

Global Connect

MINISTRY OF PORTS, SHIPPING AND WATERWAYS GOVERNMENT OF INDIA
CIVIL ENGINEERING DEPARTMENT
ADMINISTRATIVE OFFICE, HARBOUR ESTATE,
TUTICORIN - 628 004, TAMIL NADU

Telephone : 0461-2352252

Email : ce@vocport.gov.in

Website : www.vocport.gov.in

NIT (LIMITED TENDER)

(Ref:Lr.No.CIV-OFCMB-MNT-REPAI-V1-25/D. 1867 Dated: 18.06.2025)

Sub: Repair and Repainting of kerb wall and statues at CISF lawn and admin lawn area in VOCPA - Limited tender invited – (Put to tender value -Rs.4,30,680/-)

VOC Port Authority, Tuticorin desires to invite Limited tender from the following five Port Civil Engineering Contractors / firms.

1. Shri.R.T.Vairamuthu, Tuticorin-02
2. M/s.GPS Enterprises, Aundipatty-12
3. M/s.Kumar Plantations, Tuticorin-05
4. M/s.Maharaja Engineering Contractors, Tuticorin-02
5. M/s.S.Kunjan, Tuticorin-06

The above firms shall submit their duly filled-in Price Quote Schedule in a sealed cover on or before 23.06.2025 upto 15.00 hrs to the office of the undersigned in person. The Price Quote received will be opened on 24.06.2025 @15.30hrs.

As it is a Limited Tender Enquiry from the above five firms only, the bids from any other firms will not be considered.

This issues with the approval of the Competent Authority.

Encl: Price Quote Schedule.


18/06/2025
EXECUTIVE ENGINEER
(RCM & BMR DIVISION)

Name of Work: Repair and Repainting of kerb wall and statues at CISF lawn and admin lawn area in VOCPA

(Ref:Lr.No.CIV-OFCMB-MNT-REPAI-V1-25/D.1867

Dated:18.06.2025)

PRICE SCHEDULE

Name of Bidder					
Sl. No	Qty	Unit	Description of work	Rate/unit in figure & words	Amount
1	1736	Sqm	Applying One coat of Alkali Resistant Primer and Two coats of APEX - Exterior Emulsion Paint of approved colour and quality over the New wall surface in all floors to give an even shade after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand paperes smooth including all materials, labour, brushes, scaffolding, etc., complete complying with AISS andas directed by the departmental officers.		
2	192	Sqm	Plastering the Brick work 15 mm thick in Cement Mortar 1:5 (Plastering Sand (P-Sand)) (One cement, five Plastering Sand (P-Sand)) for all faces of walls (even and uneven) in all floors upto full height of the building including necessary scaffolding, racking of masonry joints, cleaning, curing etc., complete complying with AISS and as directed by the departmental officers.		
3	42	Sqm	Painting the steel surfaces with Two coats of Synthetic enamel paint of approved quality (excluding priming coat) on new steel and other metal surfaces with enamel paint, brushing, interior to give an even shade including cleaning the surface of all dirt, dust and other foreign matter including all materials, labour, brushes, etc., complete complying with AISS and as directed by the departmental officers.		
				Total Rs.	

Contractor's Signature with Seal