



வ.உ.சி.புறமுகம் ஆணையம்
वी.ओ.सी. पत्तन प्राधिकरण
V.O.C Port Authority

Global Connect

MINISTRY OF PORTS, SHIPPING AND WATERWAYS GOVERNMENT OF INDIA
CIVIL ENGINEERING DEPARTMENT
ADMINISTRATIVE OFFICE, HARBOUR ESTATE,
TUTICORIN - 628 004, TAMIL NADU

Telephone : 0461-2352252
Email : ce@vocport.gov.in
Website : www.vocport.gov.in

NIT(LIMITEDTENDER)

(Ref:CIV-RCM0ENCE(STP)/1/2025-Civil/D. 2131

Dated:07.07.2025

Sub:Installation of Bio Sewage Treatment Plant under IGBC Green Building Initiative- Civil Work -Limited tender invited - (Put to tender value -Rs. 4,98,500.00/-)

VOC Port Authority, Tuticorin desires to invite a Limited tender from the following five Port Civil Engineering Contractors/firms.

1. M/s. Maharaja Engineering, Salem
2. M/s. Surya Enterprises, Tuticorin
3. M/s. Shri Vengateswara Construction, Tuticorins
4. M/s. Sri VinayagaConstuction, Tuticorin
5. M/s. Shri Balaji Construction, Tuticorin

The above firms shall submit their duly filled-in Price Quote Schedule in a sealed cover on or before 14.07.2025 upto 15.00 hrs to the office of the undersigned in person. The Price Quote received will be opened on 15.07.2025 @15.30hrs.

As it is a Limited Tender Enquiry from the above five firms only, the bids from any other firms will not be considered.

Encl:PriceQuoteSchedule.

EXECUTIVE ENGINEER
(RCM & BMR DIVISION)

Name of Work: Installation of Bio Sewage Treatment Plant under IGBC Green Building
Initiative – Civil Work
 (Ref: CIV-RCM0ENCE(STP)/1/2025-Civil/D.213) Dated: 07.07.2025)
PRICE SCHEDULE

Name of Bidder					
Sl. No	Qty	Unit	Description of work	Rate/unit in figure & words	Amount
1	520	Cum	Earthwork in bulk excavation in dense (or) hard soil (exceeding 30cm in depth, 1.5m in width as well as 10 Sqm. on plan) including disposal of excavated soil lead upto 50m, disposed soil to be levelled and neatly dressed etc., complete complying with AISS and as directed by the departmental officers.		
2	32	Cum	Providing and laying Plain Cement Concrete 1:1.5:3 (One part of cement, One and a half parts of Coarse sand & Three Parts of graded stone aggregate (i.e.) 2 parts of 20mm nominal size graded metal & 1 part of 10mm nominal size graded metal) for RCC works using 20 mm nominal size graded metal including mixing, laying, levelling, consolidation, finishing and curing etc., complete complying with AISS and as directed by the departmental officers.		
3	1	No	Supplying and fixing of 5HP (mud pump) Kirloskar KBL make SP3L+ with 5C4 motor model size 80x80mm, 3.7KW/5HP/415V/50HZ, Selfpriming Coupled Pumpset motor. The cost inclusive of motor, labour, fixing with necessary fixtures, conveyance & functioning etc., complete and as directed by the departmental officers.		
4	20	M	Supplying and laying in trenches 110 mm dia. PVC inflow pipe line 6 Kg./CM2 with necessary pipe specials such as elbow, tee, union joint etc., and the joints being tightened including threading cost of pipe, specials etc., complete complying with AISS and as directed by the departmental officers.		

5	10	Nos	Supplying and installation of 8 ft Spray radius Pop-up type Sprinkler with necessary pipe specials such as micro filter, pressure reducer, spray nozzle, pop-up sprinkler head, flexible piping, tee-connector, sprinkler caps, etc., and the joints being tightened including cost of materials, Conveyance, installations with required specials, labour charges, tools & plants etc., complete and as directed by the departmental officers.		
				Total Rs.	

Contractor's Signature with Seal