



வ.உ.சி துறைமுக ஆணையம்
वी.ओ.सी पत्तन प्राधिकरण
V.O.C Port Authority

Global Connect
IMS - ISO 9001:2015,
ISO 14001:2015,
ISO 45001:2018 &
ISPS COMPLIANT PORT

வ.உ.சிதம்பரனார் துறைமுக ஆணையம்
वी.ओ. चिदम्बरनारपत्तनप्राधिकरण
V.O.CHIDAMBARANAR PORT AUTHORITY
पत्तन, पोतपरिवहनऔरजलमार्गमंत्रालय
CIVIL ENGINEERING DEPARTMENT
MINISTRY OF PORTS, SHIPPING AND
WATERWAYSभारतसरकार **GOVERNMENT OF INDIA**
ADMINISTRATIVE OFFICE, HARBOUR ESTATE,
TUTICORIN 628 004, TAMIL NADU

Mail & Post



SAGARMALA
PORT-LED PROSPERITY

NIT (LIMITED TENDER)

Ref: Lr.No. CIV-OFCEV-PLC-GO GR-V1-25/D. 3185

Dated: 10.10.2025

Sub: Installation of Go Green welcome Boards on the Roadside of Linkroad at
VOC Port – (Put to tender value -Rs.4,92,923/- excluding GST)

VOC Port Authority, Tuticorin desires to invite Limited tender from the following five
Port Civil Engineering Contractors / firms.

1. Shri Venkateshwara Constructions, Tuticorin.
2. M/s.Maharaja Engineering Contractors, Tuticorin.
3. M/s.Surya Enterprises, Tuticorin.
4. M/s. RS Enterprises, Tuticorin
5. M/s. JTS Engineering Works, Tuticorin.

The above firms shall submit their duly filled-in Price Quote Schedule and proof of
Earnest Money Deposit (EMD) of Rs.9,860.00 (Without EMD the tender will not be
considered) in a sealed cover on or before 21.10.2025 upto 15.00 Hrs to the office of the
undersigned in person. The Price Quote received will be opened on 22.10.2025 at 15.30
Hrs.

The above payment should be paid in the following Port Bank account:

A	Name and address of the bank	Indian Overseas Bank, Harbour Branch, Tuticorin – 628004.
B	Name of the branch	Harbour Branch
C	IFSC Code	IOBA0000143
D	Account number	014301000000001
E	Type of Account	Savings Account
F	Beneficiary's Name	V.O. Chidambaranar Port Authority

As it is a Limited Tender Enquiry from the above five firms only, the bids from any other firms will not be considered.

Encl: Price Quote Schedule.


10/10/2018

EXECUTIVE ENGINEER
(RCM & BM DIVISION)

Name of work : Installation of Go Green welcome Boards on the roadside of Linkroad at VOC Port.

Put to tender value:Rs.Rs.4,92,923/-

Ref Lr No. CIV-OFCEV-PLC-GO GR-V1-24/D.

Dated: .10.2025

Name of the Bidder					
Sl. No	Qty	Unit	Description of Work	Rate in Figures in INR	Rate in Words
1	6.100	Cum	Earthwork in bulk excavation in dense (or) hard soil (exceeding 30cm in depth, 1.5m in width as well as 10 Sqm. on plan) including disposal of excavated soil lead upto 50m, disposed soil to be levelled and neatly dressed etc., complete complying with AISS and as directed by the departmental officers.		
2	7.650	Cum	Providing and laying Plain Cement Concrete 1:1.5:3 (One part of cement, One and a half parts of Coarse sand & Three Parts of graded stone aggregate (i.e.) 2 parts of 20mm nominal size graded metal & 1 part of 10mm nominal size graded metal) for RCC works using 20 mm nominal size graded metal including mixing, laying, levelling, consolidation, finishing and curing etc., complete complying with AISS and as directed by the departmental officers.		
3	2131.500	Kg	Supplying the structural steel, MS Flats, Square Rods, Angles, Channels etc., for vertical members / bracing /stiffeners / Base plates or for any other usage as a structural member, fabricating, welding and erecting the frame work in position at the locations shown in the drawing including all labour, materials, conveyance, tools & plants, etc., complete and as directed by the departmental officers (Note : 1. While fabricating, necessary holes and bolt & nut shall be provided at no extra cost in the structural members. 2. In case, the specified MS section is not available in the market, the nearest alternative section may be used after approval of the Engineer).		

Sl. No	Qty	Unit	Description of Work	Rate in Figures in INR	Rate in Words
4	21.600	Sqm	Providing and fixing the Aluminium Composite Panels (ACP) of 3.25mm thickness for Ornamental Elevation with #3M# brand two way tape and 1.2mm thick Aluminium channels /box section of size 50 x 20mm with weight not less than 2 kg. / 12 ft. to fix the ACP, fixed rigidly with the existing wall using suitable fasteners and neatly finishing the joints with DOW corning all weather sealant grade -789 including finishing the sharp edges etc., complete as per the approved design etc., complete and as directed by the departmental officers.		
5	21.600	Sqm	Supplying & fixing Retro-reflective sticker for letters on Aluminium Composite Panel (ACP) board at all level elevation and heights. The cost inclusive of scaffolding charges, materials, labour charges & conveyance etc., Complete and as directed by the Engineer in-Charge.		
6	30.863	Sqm	Painting the steel and other metal surfaces with Two coats of ready mixed anticorrosive epoxy paint of ISI make at all location prepared and applied as per manufacture's specifications over one coat of red oxide Zine chromate priming coat surface , By spraying, interior to give an even shade, cleaning the surface of all dirt, dust and other foreign matter, cost including all epoxy painting materials, hire charges of spraying machine, brushes, labour charges, all lead & lift, handling and transportation charges, Scaffolding System and minor tools etc., complete and as directed by the Engineering in charges.		
			Total Rs.		